

ADDENDUM #1
West Street Industrial Park Project
City of Cedar Springs
EDA Project 06-01-06138

The following clarifications and additions are to be incorporated into the construction plans, bidding and contract documents:

1. All bolting inside the pump station enclosure will be stainless steel.
2. The 4-inch diameter force main riser pipe will be outfitted with a Dixon cam and groove type quick connect coupling system or approved equal. A threaded hose connection will not be required.
3. The Advertisement for Bids did not include the correct source of federal funding for this project. The reference to the Housing and Community Development Act of 1974 and Section 3 of the Housing and Urban Development Act of 1968 should be disregarded. The project is a federally funded activity authorized by the Economic Development Administration (EDA). All successful bidders must comply with the federal labor standards, including the Davis-Bacon Act and the Copeland Anti-Kickback legislation; federal equal opportunity requirements; and 2 CFR Part 200 Code of Federal requirements apply.
4. Please include two (2) additional conduits from the panel terminating at a point outside the concrete slab at the pump station. These will be for future utilities and/or SCADA system.
5. The pump station level control will be by means of a submersible transducer. An air bubbler system will not be allowed.
6. The pump station will require a remote alarm notification system utilizing a cellular modem dialer.
7. There is a conflict with the suction piping and discharge piping within the pump station wet well as they are shown on the plans. The station will be turned 90-degrees and the discharge piping will run out the back side (control panel side) of the wet well.
8. If non-hazardous soils are encountered from the old wastewater lagoon, they may be stockpiled on site and covered with a clay cap.
9. Replace Davis Bacon Wage Rate Decision number MI20210062 with the attached General Decision Number MI20220062.
10. Contractor responsible to set the electric meter socket and service line from the meter socket to the pump station. Consumers Energy will provide service to the meter socket.
11. Contract completion date may be altered to accommodate material lead time if required.

Attached are the Meeting Minutes and sign in sheet from pre-bid meeting held on January 11, 2022

Each bidder must acknowledge receipt of this addendum of the Bid Section C-410 Article 5.03.A.

END OF ADDENDUM

Prepared by:
ROWE Professional Services Company
127 S. Main Street
Mt. Pleasant, MI 48858
(989) 772-2138